



**Central Purchasing
213 South Oliver Drive
Aztec, New Mexico 87410
(505) 334-4551**

BID No. 22-23-10, Adult Detention Center Training and Wellness Center

**ADDENDUM #2
October 26, 2022**

**CLARIFICATION / ADDITIONAL INFORMATION FOR BID SPECIFICATIONS AS
FOLLOWS:**

- Changes and clarification to the bid specifications have been made pursuant to the attached addendum sheets as provided by Rodahl & Hummell Architecture (1 page).

Plan Holders List:

Bidders are reminded that in order to obtain the most current and up to date listing of plan holders, you are encouraged to visit the County's Website at www.sjcounty.net.

PLEASE ACKNOWLEDGE RECEIPT OF THIS ADDENDUM ON THE OFFER PAGE.

Addendum #2
Adult Detention Center Training & Wellness

609 N. Dustin Avenue
Farmington, NM 87401
(505) 326-6442

October 25, 2022

This addendum takes precedence over work shown on the Plans and described in the Specifications and shall become a part of the Contract Documents. All work not specifically noted as changed or modified shall be furnished and installed as shown on original Drawings and as outlined in the original specifications.

- Item #1: Detail A/S1. Clarification. Grade adjacent to the building does not need to be "native clay". Provide re-compacted native soils or aggregate base course materials for this top 12" of material. The 4" perforated rigid piping and wrap is not required.
- Item #2: Sheet A7. Equipment Schedule. Note #2. Change to "Roller Shades. See Specification Section 12 2413.
- Item #3: A6. Reflected Ceiling Plan. Other than bearing walls those which will extend to roof deck with 3" slip track connection include:
1. Hallway 107 both sides.
 2. Wall above folding partition between 103/104. See Detail 1/A6.
 3. All walls around IT Room 102A.
- Item #4: Sheet A1.1. Finish Material Key. Ceramic Tile (type W2) shall be Daltile, Kimona Silk, 12x24, run long side vertical. Also acceptable are Daltile Fabrique and Timber Glen with non-sanded grout. Colors to be selected. See Detail 1/A1.1 for extent.
- Item #5: Sheet A0. Provide a 24" x4" thick concrete slab adjacent to the building wall anywhere that is not now shown to have concrete paving. Slab to be 1" below F.F. and slope away from the building 3" minimum.

End of Addendum #2

PRIOR APPROVALS:

The following materials/manufacturers have been approved for use in lieu of those specified in the Contract Documents.

Specification Section	Item	Approved Supplier
10 5113	Metal Lockers	Scranton Products